

Pre-Installation Checklist

Prior to installing the AutoGuard® and PowerTouch series automatic pool cover, make sure the pool site is prepared properly and is ready for the installation of the cover. Jobsite is ready for installation when all the items have been checked. Complete pool site preparation will ensure that the AutoGuard® and PowerTouch automatic pool cover systems can be properly installed. Please check off all items for site readiness.

- Water level is at normal operating level (middle of skimmer).
- Assess if there are any potential obstructions (i.e. grab rails, ladders, slides, sports poles, fountains) for running the automatic cover.
- Deck has been completed and secured (no pavers) with plenty of room for track and lid assembly.
- Recessed box is free of concrete, nails, or any other type of obstruction.
- Recessed box is correct height, width, and length. Box is square to pool.
- Electrical and remote keyswitch wires are in place with GFCI protection.
- Retainer is free of debris and/or concrete (if applicable).
- Measurement of pool track space, track length, and diagonal are consistent with order.
- Pool bonding wire in place (if applicable).
- Proper and adequate drainage in recessed box to remove ground water quickly.

Once you have checked off all of the above boxes, you are ready to install your auto cover. When you receive your AutoGuard® or PowerTouch series automatic pool cover, inspect all delivered parts to ensure accuracy and that all items are included for the installation. If any items are missing or damaged, call your automatic pool cover supplier immediately. Visually inspect all contents for any damage and that all items are included. Open any accessory boxes and look over documentation to make sure what was ordered, measured, and received are all within the range of acceptance. Also, confirm fabric color. *Note: The fabric is often times wrapped in a different color than what was ordered.* Measure all extrusions and cover to ensure accuracy with final pool measurements. Cover will be approximately 6" - 9" wider than the track space.

If All Boxes Are Checked Off, The Install Should Be Ready to Go!